

Absolute energy calibration of FD by an electron linear accelerator for TA



Tatsunobu Shibata

Institute for Cosmic Ray, University of Tokyo

2010.12.10(Fri)

Energy Measurement with FD


Air Shower by Primary Cosmic Ray

② Atmospheric Attenuation Scattering and Absorption


① Fluorescence Light

Energy loss to
Fluorescence photons

$$\Delta E \rightarrow N_{\text{photon}}$$



N_{photon}
 N'_{photon}



③ Fluorescence Telescope

Photons to ADC count

$$N'_{\text{photon}} \rightarrow N_{\text{ADC}}$$

④ Out of FoV, Missing Energy



Systematic Uncertainty of TAFD Energy Scale



Systematic errors

TA-FD Hybrid Analysis,
2010.March.JPS, presented by D.Ikeda

Item	Systematic error
Fluorescence yield	12%
Detector	10%
Atmosphere	11%
Primary particle mass	5%
MC correction	3%
Total	19%

➔ **Main Large Systematics**


**End-to-End Calibration
Need !!**

Electron Light Source (ELS)


Energy Scale of Telescope Array (TA) experiment

= Decided by Electron Beam from LINAC(ELS) near FD site

Electron Light Source (ELS) = A unique absolute energy calibration



ELS is located at 100m far from FD



Known beam energy = We can estimate energy deposit in the
 We can calibrate all of FD calibration constant = End-to-End Calibration



The Specification of ELS

■ Energy : 40MeV

The electron energy in 10^{20}eV Air Shower
($10\text{MeV} \sim 1\text{GeV}$)

■ Position : 100m far from FD

Range of 40MeV electron \sim FoV of TA-FD

■ Current : $10^9\text{e}^-/\text{pulse}$

10^{20}eV Air shower 10km far from FD


$\rightarrow 10^{16}\text{eV} @ 100\text{m} \rightarrow 10^{16}\text{eV} / 4 \times 10^7\text{eV} \sim 10^9\text{e}^-$

■ Pulse Width : $1\mu\text{sec}$

Time scale of signal of air shower in $\sim 1\text{PMT}$

Development of ELS

ELS was developed in KEK




Design of ELS

RF System
Frequency=2856MHz
Output Power~20MW

Use Non Frozen water : Propylene Glycol solution

20kW Cooling Unit
30°C, 110L/min



(Buncher, Accelerator Tube, Focus Magnets, Steering Coils.)

Installation RF system and Accelerator Unit into the 40ft container

Cooling Unit into the 20ft container


Construction of ELS in KEK injector

- Construction Apr.2005 - Jan.2008
- Beam Operation '08.Feb.22th - Dec.10th

Beam Condition

- Repetition $\sim 0.5\text{Hz}$
- Energy $\sim 40\text{MeV}$
- Current
 $10 \sim 250\text{pC/pulse}$


Built in
Shield room



This photo was taken in '08.Dec.24 after removal all Shields.

Final Figure of ELS at KEK

Final Reconstruction of ELS was completed in KEK, Feb.'09



Shipment of ELS KEK to U.S.

ELS was moved w/o disassembly



2009. Feb.23rd (Mon) Carried out from KEK

Mar.19th (Thu) Installation of ELS into FD site

ELS Standby in FD site



ELS Site at FD Site

Feb-Mar.2009 ELS was installed at the FD Site 100m far from FD

Apr.2009 – May.2010 Setup the infrastructure of the ELS

Jun-Sep.2010 Standby of the ELS Beam Operation

Beam Shot Direction

Radiation Controlled Area

ELS Control Room

Optical LAN cable is connected from FD site.

EL

Concrete Shield
2ft-thick, 12ft-height

Generator (80kW)
Power for ELS operation
~50kW

Keep power for
Air Condition and Vacuum
from generator in FD site.

Cooling Unit Container

Taken the picture in Sep.5th.2010 from top of the FD station

Administrator : University of Utah

Radiation Safety Officer (RSO)

Responsible User(RU)

Onsite-Radiation Safety
Officer (Onsite-RSO)
Onsite-Responsible
User(Onsite-RU)

- ◆ Need ≥ 2 persons
(Onsite-RSO $\times 1$ + Onsite-RU $\times 1$)
- ◆ All people need license of
Radiation worker

Radiation Protection



First Shot and Detection by FD



Event Display of ELS Shower

Data : Sep.5th .2010.
AM04:30(UTC)

Energy : 41.1MeV

Charge : 50pC/pulse

First
Shot!!! In
Sep. 2010
DATA



Beam Operation : Sep.2nd -4th

Beam shot into the Sky : Sep. 3rd and 4th

of Shot into the Sky ~ 1800 pulses



Output power = $41.4\text{MeV} \times 40 \sim 140\text{pC/pulse} \times 0.5\text{Hz}$

Data Analysis


Energy Calibration w/ ELS

Energy Calibration =
Comparison of MC simulation and DATA

$N_{\text{p.e.}}^{\text{DATA}}$



$$\sum_{i=1}^{256} (N_{\text{p.e.}}^{\text{DATA}})_i$$



Change the beam charge

$$\sum_{i=1}^{256} (N_{\text{p.e.}}^{\text{MC}})_i$$

$$\left[\sum_{i=1}^{256} (N_{\text{p.e.}}^{\text{MC}})_i \right]^{\text{corr}}$$

$i = \text{PMT\#}$

$$= \underbrace{f_{\text{calib}}}_{\text{Correction factor, constant}} \times \sum_{i=1}^{256} (N_{\text{p.e.}}^{\text{MC}})_i + \underbrace{c_{\text{calib}}}_{\text{Correction factor, constant}}$$

Correction factor, constant

Correction of MC used the correction factor and constant



Energy Calibration w/ ELS

Real Data

- ELS Data

- Beam monitor (Time, Energy, Beam Current)

- FD Data

- Shower data which is observed with FD
- Environment condition (Temperature, Pressure, Humidity, ...)

Weather station at FD site

MC Data

- Shower Simulation


- Air shower simulation by using Geant4

We want to use more than two codes for double check of "Energy deposit" in the air.


- FD Simulation

Performance the Air Shower

(1) Longitudinal distribution





(2) The scattering angle of primary electrons



The distribution depends on temperature(density of air)
 → This effect is small in the FoV (height : 10m~70m)

Data Checking

Data set : Taken in Sep.5th (UTC)
checking now...



Systematics Improvement

■ Fluorescence Yield(12% \rightarrow \sim a few %)

In ideal, the systematic uncertainties becomes to be zero.

-The uncertainties of the spectrum remains \sim a few % ?

■ Fluorescence Detector (10% \rightarrow \sim a few % ?)

In ideal, the systematic uncertainties becomes to be zero.

-The FDs which can not be calibrated by ELS will be calibrated by relative calibration with laser system \sim a few % ?

■ ELS(\sim 4%)

- The uncertainty of output energy can be ignored.

... in case of $40 \pm 2\text{MeV} \rightarrow$ # of detected photons $< 1\%$ difference.

-The uncertainty of the beam charge = 4% (beam test in KEK)

Improved Systematics $< 10\% \rightarrow$ The total systematics $\sim 10\% + \alpha$



Operation of ELS

■ We will operate ELS for calibration every about 2 month

We want to calibrate FD in different air condition,
and study their dependence, and time variation.

But we need – Beam conditioning.

(next week ... in Utah)

Beam direction, position monitor,
Energy, Current measurement...

– More Data Checking, and MC study.



Potential of ELS

■ Standard energy calibration source for UHECR observation

■ Fluorescence experiment

■ Radio Detection

■ And your ideal ...



Summary

Motivation of ELS (Electron Light Source)

Absolute Energy Calibration

(Calibrate all of calibration constants by one source)

= End-to-End Calibration

Status of ELS

Sep.2010 First Shot was Detected !!!!!

On Going!!!

Started Energy calibration by ELS!!!!

- Shower simulation by using Geant4 → checking their performance.
- Data Analysis → checking.